



Price Bid

Current Tender Details

IFB / Tender Notice No : MDCMPUL/ 2018-19/ 44/Generator / 1450KVA GG-1

Tender ID: 339594

Name of Work : Dismantling and Shifting of 1450 KVA Gas Generator set's electrical panel, cooling tower, piping with GEB approval from Jagudan Cattlefeed plant to Dudhsagar Dairy, Mehsana plant and Re Installation and Commissioning at Mehsana District Cooperative Milk Producer's Union Ltd., Dudhsagar Dairy, Mehsana

ECV (INR): 2100000.00

Last Date & Time For Submission of Bid: 17/01/2019 17:00:00

Type Of Tender: open

Price Bid

Sl. I	Item Description	Quantity	Unit	Unit Rate	GST (in Percentage)	GST (in Rs.)	Net Amount (Rs.)
(A) Services							
1	Dismantle all electrical/electronic panels of 1450 KVA GG Set-1 from Jagudan CFP and shifting /install at Dudhsagar Dairy, Mehsana generator section.	1	Job			0	0
2	Laying and termination of cables from generator panels to L.T. panels of electrical section with earthing (body and neutral)	1	Job			0	0
3	Re use and remaking or re assemble of all piping for generator, cooling towers and wet ventilation room etc. From Jagudan CFP and shifting /install at Dudhsagar Dairy, Mehsana generator section.	1	Job			0	0
4	Commissioning of 1450 KVA GG set on load with electrical inspector approval.	1	Job			0	0
5	400 sq.mm x 3.5 core cable laying charges	1650	Meter			0	0
6	1 Meter x 1 Meter land excavation ,removing rubber block ,sand filling, bricks to be laid charges	275	Meter			0	0
7	Fixing of rubber block charges	2200	Sq. ft.			0	0
8	RCC digging charges	12	RMT			0	0
9	400 sq.mm x3.5 core cable termination charges(two end,6nos cable)	2	Nos.			0	0
(B) Supply :							
1	Supply of 400 sq.mmx3.5 core aluminum armored cable,1100v, grade: XLPE, Make: Avocab OR RR	1700	Meter			0	0
	Supply and installation of earthing: chemical earthing, zero						

2 maintenance, 250
micron, copper with
certificate, Make:
National GI strip
size: 50x5mm hot
drip.

1

Job

		0	0
--	--	---	---

0

zero

Documents Required

There are no Documents

Close

Server Time : 22/12/2018 15:17:23