

## MEHSANA DISTRICT CO-OPERATIVE MILK PRODUCERS' UNION LIMITED

MEHSANA 384002 India Phone: 02762-253201 TO 253205 REQUEST FOR QUOTATION

(ISO Doc No:)

One Time Vendor	4000010	RFQ No.:	M630021476 Date: 04.05.2021			
		Collective No.:	0000202333			
		Doc. Type:	ZR03 Service RFQ			
India		POrg:	MP00 Central PORG-Mehsana			
		PGroup:	M08 S/C & Service			
		Quotation Deadline:	15.05.2021			
		Our Reference:	Kheralu			
		Created By :	ENGPUR MEH			
Your GSTN :		Our GSTN : 24AAAAM0329F1Z6				

Dear Sir,

We invite quotation for supply of following items:

Subject: Purchase Enquiry for Material Group

Sr. No.	Activity	HSN/S AC	Short Text	Qty	OUn	Delivery Date	Plant	Mat. Grp
1			Osp Job work for Breaker Services.	1	AU	20.05.2021	ML03	SR0000002
	100531		Electrical Maintenance Osp Job.	10	AU			

Goods to be supplied subject to terms and conditions as per enclosed Annexure/s.

Please ensure that your sealed quotation reach us before deadline date, complete with necessary annexure.

Thanking You,

For, Purchase Department MEHSANA DISTRICT CO-OPERATIVE MILK PRODUCERS' UNION LIMITED



# MEHSANA DISTRICT CO-OPERATIVE MILK PRODUCERS' UNION LIMITED

MEHSANA 384002 India Phone: 02762-253201 TO 253205 REQUEST FOR QUOTATION

(ISO Doc No:)

RFQ:	M630021476	Annexure : 1					
Date:	04.05.2021						
Delive	Delivery Location, Item Classification and Item text						
			ı				
Item	Material	Material Description					
1	Plant: ML03	Osp Job work for Breaker Services.	I				
	Osp Job work for Brea	Chilling Center, Kheralu Kheralu chilling center,,Mehsana,384325					
	Osp. Service/repaire ic	bb work regarding misca. L&T make CN-CS Type Air Circut Breaker IN DIFFERENT electrical panel board at					
	our Kheralu Milk Chillir	ob work regarding misca. L&T make CN-CS Type Air Circut Breaker IN DIFFERENT electrical panel board at ng Center.					
	Work scope conditions						
	FOLLOWING MCCB L	LIST:-					
	(2 LT LINE 2500AMP.)	CN-CS2500S1, AIR CIRCUIT BREAKER,L&T =03 No. CN-CS2500C, AIR CIRCUIT BREAKER,L&T =01 No.					
	(3)LT LINE 2000AMP.	CN-CS2000S1, AIR CIRCUIT BREAKER,L&T =01 No. CN-CS1250S1, AIR CIRCUIT BREAKER,L&T =01 No.					
	(4)LT LINE 1250AMP.	CN-CS1250S1, AIR CIRCUIT BREAKER,L&T =01 No. CN-CS1000C. AIR CIRCUIT BREAKER,L&T =02 No.					
	(6)LT LINE 800AMP.C	CN-CS1000C, AIR CIRCUIT BREAKER,L&T =02 No. CN-CS800S1, AIR CIRCUIT BREAKER,L&T =02 No.					
	Kindly Contact Mr. D S	S Thakor 81286 74039 [for Material Detail, OSP Job & Technical Discussion only]					
Goods	to be supplied subject	ct to terms and conditions available at http://www.dudhsagardairy.coop/tenders/					
20000	so cappiloa dabjet	2. 10 10 Sala containen aranasio ar mapin minadanoagardan y.ooop.tondoloi					





#### MILK CHILLING CENTER, KHERALU

#### MEHSANA DISTRICT CO-OPERATIVE MILK PRODUCER'S UNION LIMITED

KHERALU.Pin-384325 Ph.: 02761 231012, CUG Mobile No: 8128674066

**Annexure-:- Scope of work** 

### **SCOPE OF WORK FOR SERVICING OF ALL TYPE ACB**

- 1. To Clean ACB by using CRC 226.
- 2. To remove old grease & re-greasing with recommended (Standard) grease.
- **3.** To check & service the condition of arcing contact & gap between fixed & moving arcing contacts.
- **4.** To check & service the reset mech., tripping of breaker through PB.
- **5.** To check & service tripping of breaker through releases.
- **6.** To check & service freenes of release trip rods.
- 7. To check presence & tightness of hardware.
- **8.** To check presence of all circlips.
- 9. To check & service condition & alignment of jaw contact and cradle terminals.
- **10.** To check & service condition of ACB, VCB wiring & replace if required.
- **11.** To check proper closing of all poles together.
- **12.** To check of antipumping in case of EDO ACB.
- 13. To check & service alignment of SIC & its operation.
- **14.** To check condition of ARC chutes.
- **15.** To check & service motor & closing operation in case of EDO ACB.
- **16.** To check continuity & proper changeover sequence of aux. contacts.
- 17. To check resistant (Megering) of ACB phase to phase with earth & pole I/C & O/G.
- **18.** To check & service DIN rail freenes for racking of breaker in cradle.
- **19.** To measure CT'S resistance.
- **20.** To check release setting as per load condition.
- **21.** To check release through secondary injection.
- **22.** Party should have to use standard "L&T service kit" for the all above job works.
- 23. If any spares parts broken during service then it is only in party's scope to replace it.
- **24.** Broken Bezel Replaced by vendor covered in Service.