

# DUDHSAGAR RESEARCH AND DEVELOPMENT ASSOCIATION

MEHSANA 384002 India  
Phone: 02762-253201 TO 05  
REQUEST FOR QUOTATION

(ISO Doc No : )

<b>One Time Vendor</b>	4000010	<b>RFQ No.:</b>	M963000038    Date: 08.09.2021
India		<b>Collective No.:</b>	0000217032
		<b>Doc. Type:</b>	ZR03 Service RFQ
		<b>POrg:</b>	MP00 Central PORG-Mehsana
		<b>PGroup:</b>	M11 Engg Spr purchase
		<b>Quotation Deadline:</b>	22.09.2021
		<b>Our Reference:</b>	jagudan Psk
		<b>Created By :</b>	ENGPUR MEH
<b>Your GSTN :</b>		<b>Our GSTN : 24AAATD1312J1ZA</b>	

Dear Sir,

We invite quotation for supply of following items:

Subject: Purchase Enquiry for Material Group

Sr. No.	Activity	HSN/S AC	Short Text	Qty	OUn	Delivery Date	Plant	Mat. Grp
1	100658	995413	Civil And Structural Work For G.I. Sheet Civil Work	1 1	AU AU	11.10.2021	MR01	CP0000006

Goods to be supplied subject to terms and conditions as per enclosed Annexure/s.

Please ensure that your sealed quotation reach us before deadline date, complete with necessary annexure.

Thanking You,

For, Purchase Department  
DUDHSAGAR RESEARCH AND DEVELOPMENT ASSOCIATION

# DUDHSAGAR RESEARCH AND DEVELOPMENT ASSOCIATION

MEHSANA 384002 India  
Phone: 02762-253201 TO 05  
REQUEST FOR QUOTATION

(ISO Doc No : )

RFQ: M963000038

Annexure : 1

Date: 08.09.2021

Delivery Location, Item Classification and Item text

Item	Material	Material Description
1		Civil And Structural Work For G.I. Sheet

Plant: MR01 Pashu Samvardhan Kendra , JAGU ,Near Toll Plaza State Highway,Jagudan,382710

Civil And Structural Work For G.I. Sheets The PSK Jagudan old Building behind Open area Parcking Shed at PSK Jagudan.

Kindly Contact Mr . A.Y fatteh-8128673980 [for Material Detail, OSP Job & Technical Discussion only]

Kindly call our officer between 9:00 A.M. to 05:00 P.M. only

Kindly Give rate on FOR our Mehsana Plant bases, inclusive of Freight Charges

**Through Courier**

**Dudhsagar Research and Development Association, Mehsana – 384002.**

No. Civil/ Tender/

Date:-

Name of contractor:

Sub :- Name of work **Civil And Structural Work For G.I. Sheets The PSK Jagudan old Building behind Open area Parcking Shed at PSK Jagudan.**

Dear Sir,

We are pleased to invite tenders for **Civil And Structural Work For G.I. Sheets The PSK Jagudan old Building behind Open area Parcking Shed at PSK Jagudan.** We request you to kindly send your sealed tender in the blank tender form enclosed herewith. You are requested to go through the special notes on bill of quantities enclosed herewith before submitting the tender. You are also requested to visit the site and refer the drawings before submitting your tender,

The filled tender shall be submitted to us on or before date ----- on the above mentioned address along with a Demand Draft of Rs. **10000/-** in favour of "MEHSANA **DISTRICT CO-OPERATIVE MILK PRODUCERS' UNION LIMITED.**" The name of the work shall be written clearly on tender envelope along with the last date of submission. For any query ,pl contact **sh.Kalpesh Desai.**, Mobile No:**9974568903** civil deptt.

The union reserves its rights to reject wholly or partly, one or all the tenders without giving any reason.

Thanking You,

Yours faithfully,  
For Mehsana DCMPU Ltd;

Head Purchase

Encl : As above

**Dudhsagar Research and Development Association, Mehsana.**

**SPECIAL NOTES ON BILLS OF QUANTITIES**

1. Works included in all bills of quantities shall be carried out as described in the Indian Standard Code of practice for respective items.
2. The rates for the items in all bills shall include all requirements of the specifications whether such requirements are mentioned in the bill of quantities or not.
3. The quantities mention in this bill of quantities are approximate and are given as a guide to tenderers and are liable for variation up to 10% of total Amount of work for higher side . Such variation in quantities shall not, however, vitiate the contract in any way whatsoever and the contractor shall be paid for the actual measured quantities of work executed at the rate given in the bills of quantities.
4. Rates quoted shall include all the operations, material, labour, tools, plants, tackles, scaffolding and other sundries etc. required to complete the job.
5. Rates quoted shall include GST ,royalty, monopoly charges and any other taxes, duties, surcharge etc. levied by the govt. or local bodies from time to time.
6. The execution drawings may need to be revised from time to time to suit the site requirements. Such changes will not entitle the contractor for any extra payment or compensation other than executed and measured work.
7. The rates quoted for various items of work shall include working in all conditions at any time till the completion of work including all suspension period and delays whatsoever.
8. The rates quoted unless otherwise specified shall include work in all shapes, straight, inclined, curved etc. and all sizes as shown or as required.
9. The contractor must see the site condition, drawings and take all the aforesaid factors and foregoing factors stated under various trade sections while quoting the rates, as no extra rates / charges will be allowed on any ground arising out of or relating to the aforesaid and foregoing factors.
10. Basic rates of materials shall be as under.

<b>Sr</b>	<b>Item</b>	<b>Unit</b>	<b>Basic rate (in Rs.) F.O.R. as per market</b>	<b>The rate is including F.O.R. at site including GST, Transportation, Loading ,unloading etc</b>
1	Cement	Per bag	<b>320.00</b>	
2	Mild steel	Per Kg.	<b>70.00</b>	
3	TOR steel	Per Kg.	<b>58.00</b>	
4	Structural steel	Per Kg.	<b>58.00</b>	

Whatever the basic rates(including loading, unloading, Transportation up to Dairy site) are specified for the material to be used in the work, the same shall be procured by Contractor. Union reserves the right to purchase and issue the same material to the contractor. In case, any abnormal condition arises, the Union may be purchased the same. Before the purchase of material ,The contractor must obtain prior approval of the union for Make ,grade and submit quotations/bills obtained from the suppliers for basic rates items during submission of Running bills or final bill of the work. The Union shall not be paid any rate difference for basis rates items and No any price escalation for this work.

11. If water or power or both are provided by the Union, the consumption charges will be deducted from the bill at the rate as mentioned below respectively. (It will be provided by suitable outlet point, from where contractor has to arrange his own means)
  - a) Water Charges : 0.5 % of work done
  - b) Electrical Charges: : 0.5 % of work doneOtherwise, Contractor has to arrange them on their own.

12. **PAYMENT:**

- a) The contractor will submit a bill in approved Performa in triplicate to the Union for the work given, in standard abstract and measurement sheet for various items executed once in a month or on the completion of the work.
- b) In case of any dispute as to the mode of measurements, Indian Standard Specifications shall be followed.
- c) All the running accounts payable shall be regarded as payment by way of advance against the final bill and The advance payments to be settled against actual work done when work to be completed.
- d) **Payment of Contractor's Running Bill. :**
  - i) This payment will be made after making necessary checking and deductions.
  - ii) Retention money will be deducted at the rate of 7.5 % of the billed amount. Retention Money shall be released as under.
    - A) 5.0 % on settlement of final bill.
    - B) 2.5% on completion of defect liability period i.e. 6 month after completion certificate. (Shall be retained as Performance Security for this period.)
    - C) The bidder/contractor shall request to release EMD/retention money within one year after defect liability period as mentioned.
13. Within one month of the completion of the work in all respect, the contractor shall be furnished with a certificate, but no certificate shall be given until all scaffolding, surplus material plant, rubbish etc. is cleared off the site completely or the work have been measured.
14. The contractor will maintain stock register for the material provided by the Union/contractor and maintain its stock on day to day basis.
15. The contractor shall at his expense comply with all labour laws, safety regulations and required insurance and keep the Union indemnified in respect thereof.
16. The time limit for the specified work is 30 days.
17. The successful bidder has to start the work within 15 days on receipt of work order/intimation by the civil department.
18. EMD of unsuccessful bidder shall be released after issuing order to successful bidder.
19. Penalty for the delayed work will be imposed on the basis of 0.5 % per week of the total work executed and maximum up to 5% of the total work executed of the project, in case of delayed or incomplete work for the time beyond the prescribed time limit.
20. In case, work is not initiated after getting the work order within stipulated time limit without giving legitimate reasons, then EMD / performance security will be forfeited by the Union and the work will be completed on the risk and cost of the contractor.
21. In case, part work is done by the contractor and then refuse to complete the work without giving any legitimate reason, then the work will be completed on the risk and cost of the contractor. The Union may without prejudice to any other method of recovery, deduct the amount of such work from any payments in its hands due or which may be due to the contractor for this work or any other work.
22. General guidelines of EMS issued to the contractor from time to time should be followed.
23. The contractor shall give the work schedule with in 15 days of start of the work and shall work as per the guideline of user department or civil department.
24. For any dispute, respective Indian standard code will be followed. For any other dispute, decision of Managing Director of the Union will be binding on the contractor.
25. The contractor shall provide GST/Service tax number with quotation. In case of any dispute, Mehsana shall be the jurisdiction.

Head (Civil)  
Dudhsagar Dairy, Mehsana

Sign and Seal of the Contractor  
Address : \_\_\_\_\_  
Mobile Number: \_\_\_\_\_

**Dudhsagar Research and Development Association, Mehsana.**

**SOQ**

**Name of work :- Civil And Structural Work For G.I. Sheets The PSK Jagudan old Building behind Open area Parcking Shed at PSK Jagudan.**

<b>No.</b>	<b>Items</b>	<b>Unit</b>	<b>Qty</b>	<b>Rate</b>	<b>Amount</b>
1.00	Excavation in all types of soil, including murum, for foundations of wall, columns, plinth beams, basement, raft ducts, trenches, underground sumps, septic tanks etc. including shoring strutting, bailing out water/pumping off water if required, refilling the trenches, foundatin pits, ramming, watering consolidating in 15 cms to 20 cms layers, removing and stacking simultaneously the excavated stuff as directed within the site area upto a lead of 500 m and/or spreading soils in layers for site development and consolidating as directed etc. complete.				
	From existing ground level up to 1.5M depth	CUM	12.00		
2.00	Surface dressing including preparation of sub grade of road floor bringing earth work to required grade, slope and chamber including cutting or filling earth up to 300mm thickness, watering, consolidation with 10 MT Power Road Roller etc. complete as per details as directed.	SQM	25.00		
3.00	Providing & Laying in a compact manner 20 cms thick (Average) rubble soling in plinth using average 100 to 150 mm size stones, including filling in the voids with largest possible stones, covering & leveling the surface with layers of coarse sand well watered and consolidated etc. all complete as directed.	CUM	6.00		
4.00	Providing and laying machine mixed cement concrete in volumetric proportion 1:4:8 ( 1 cement : 4 coarse sand : 8 black trap stone aggregates 37 mm and down) for specified thickness, for foundations below walls, column footings, sunk floor, terraces at any height above plinth level, raft at any depth, below floors, pavements, roads, plinth protection, etc. including centering and shuttering if required, laying spreading, ramming, consolidating as per requirement and curing etc. complete as directed.	CUM	6.00		
5.00	Providing and laying in position machine mixed and machine vibrated reinforced cement concrete conforming to M25 (1:1:2) grade concrete at any depth below ground level but up to plinth level for structural elements, viz. Foundations, footings, raft, footing beams etc as per structural design & as directed using 20mm down graded machine crushed black trap stone aggregate including design of concrete mixes, weigh batched proportioning including necessary centering and shuttering at any lift and lead as specified finishing concrete surfaces, curing etc. complete but excluding of reinforcement steel etc. complete as directed. TMT Reinforcement steel will be measured and paid in relevant items.	CUM	7.00		

No.	Items	Unit	Qty	Rate	Amount
6.00	Providing, fabricating & fixing in place and position reinforcement TMT steel bars of Fe 500 Grade for RCC structures as per design including transporting steel from site stores (within site premises) to the work site, unloading cutting, bending and binding with 16 to 18 gauge annealed soft G.I. wires (to be supplied by the contractor at his own cost) welding if necessary etc complete as directed. Payment will be made on the length basis and standard co efficient to convert in to weight as per IS Standerd. (Rolling margins and wastages will not be paid).	KG	345.00		
7.00	Providing and constructing brick masonry in CM 1:6 ( 1 cement & 6 coarse sand ) with approved first class bricks having minimum crushing strength of 40-50 kg/sq.cm including scaffolding, racking out the joints, curing, forming Holes, Zaries, Cutout, Openings, projected pattas etc. Complete as directed by Engineer - in charge. For foundation at all levels below and upto plinth level.	CUM	1.00		
8.00	Providing and applying 12m thick cement finish plaster at all heights, all floors and below plinth in 1:4 cement mortar to the walls, beams, ceiling, stair , column, pardis, bends, moulds, pattas, grooves including scaffolding, curing & finishing smooth. The plaster surface shall be rubbed with "Iron plate" , till the surface shows cement paste in line and level complete as directed.	SQM	5.00		
9.00	Providing, fabricating and fixing in position MS inserts such as nosing, corner angles of columns, plates, flats, tees, protection channels of reception dock, provision for pipe hangers, supports, brackets and monorails, hooks, frame around cut-out MS pipe sleeves as per drawings and specifications, in true line and level including embedding the same into the permanent works at the time of casting of RCC works with necessary welding, grinding and painting with two coat of first quality synthetic enamel paint of make J&N / Shalimar/ British/ Asian, over a coat of primer etc. complete as directed.	KG	500.00		
10.00	Providing ,fabricating & fixing of G.I. sheet roofing/sheet cladding including ridges, hipsvalleys and gutters etc., Sheets of approved make in roofing and clading fixed with self tapping screw and stiching bolts at approx. 450 mm c/c etc with metal bond EPDM washer & HDPVC cap etc. complete including all cuts,mitered ,joints and overlap etc.as directed.	SQM	25.00		

No.	Items	Unit	Qty	Rate	Amount
11.00	Providing & fixing GI roof gutter of size 300 mm width, depth 150mm - 300 mm as per detail, laid in required slope, made out from 16 gauge GI sheet and fixed by 50 x 8mm MS flat Clamps, make the joints water tight, reveting, with p & A two coats of Enamel paint over one coat of Red oxide primer, making holes for Rain water pipe etc complete as directed by engineer - in -charge. (M.S. flats will be paid in structural steel item)	RMT	7.00		
12.00	Providing, laying and fixing in line, level and slope as per requirement inter locking colored C.C paver block fixing in pattern as per details and design having block thickness 75mm to 80mm with compressive strength 40 N/nM2 and water absorption less than 3% and wear resistance of under 2mm including laying and fixing paver block on good quality river sand layer of approx. 25mm to 40mm thick over prepared base and filling the joints and edges at ends in C.M. (1:2), curing, all tools and tackles etc. complete as directed.	SQM	25.00		
13.00	Providing and applying white washing with lime on old/ new work surface with three or more coats to give an even shade to walls, ceiling, AC sheets etc., including adding of glue of pidilite Co., or of equivalent, Indigo (blue) make (last two coats shall be applied with brush only) for all floors, heights and levels.	SQM	5.00		
14.00	Providing and applying "Apex" or "weather coat" of Asian or British exterior grade paints to exterior surfaces of walls including cleaning old plastered surface/new wall with wire brush, two or more coats of approved shade etc for all floors, heights and levels as directed.Note:The measurement shall be paid as per sand face plaster work and no extra measurements/ claims shall be paid for rough surfaces.	SQM	10.00		
15.00	Dismantling PCC/ brick bats coba w.p. in floor as per instructions including finishing the broken surface to match with the surroundings. Disposing debris/ muck as directed within the site or as directed by Eng. Incharge etc. complete as directed.	CUM	1.00		
16.00	Dismantling stone/Brick masonry walls or partition wall plastered or un plastered as per instructions including finishing the broken surface to match with the surroundings, removal and disposal of debries within site including cutting the reinforcement bars, if any etc. complete as directed.	CUM	1.00		
17.00	Dismantling the RCC beams, slabs, lintels, columns, pardi walls, platform etc. including finishing the broken surface to match with the surrounding, removing the debris within site, including cutting the reinforcement if any etc. complete as directed.	CUM	1.00		
				<b>Total Rs.</b>	
				<b>GST 18%</b>	
				<b>NET AMOUNT RS.</b>	

Head Purchase  
Dudhsagar Dairy, Mehsana

Sign and Seal of the Contractor