



MEHSANA DISTRICT CO-OPERATIVE MILK PRODUCERS' UNION LIMITED

MEHSANA 384002 India
Phone: 02762-253201 TO 253205
REQUEST FOR QUOTATION

(ISO Doc No :)

One Time Vendor	4000010	RFQ No.:	M610133801	Date: 19.11.2021
India		Collective No.:	0000225016	
		Doc. Type:	ZR01 Manual RFQ - Mat	
		POrg:	MP00 Central PORG-Mehsana	
		PGroup:	M05 Cap Goods Purchase	
		Quotation Deadline:	30.11.2021	
		Our Reference:	VCC BoreKAM	
		Created By :	K.A.Mehta/ Jyotirmoy	
Your GSTN :		Our GSTN :	24AAAAM0329F1Z6	

Dear Sir,

We invite quotation for supply of following items:

Subject: Purchase Enquiry for Materials

Sr. No.	Material	HSN/S AC	Short Text	Qty	OUn	Delivery Date	Plant	Mat. Grp
1	4016581	39172190	WATER BOREWELL FOR VIHAR CC PLANT	1	EA	30.12.2021	MM03	CP0000001

Goods to be supplied subject to terms and conditions as per enclosed Annexure/s.

Please ensure that your sealed quotation reach us before deadline date, complete with necessary annexure.

Thanking You,

For, Purchase Department
MEHSANA DISTRICT CO-OPERATIVE MILK PRODUCERS' UNION LIMITED



MEHSANA DISTRICT CO-OPERATIVE MILK PRODUCERS' UNION LIMITED

MEHSANA 384002 India
Phone: 02762-253201 TO 253205
REQUEST FOR QUOTATION

(ISO Doc No :)

RFQ: M610133801

Annexure : 1

Date: 19.11.2021

Delivery Location, Item Classification and Item text

Item	Material	Material Description
1	4016581	WATER BOREWELL FOR VIHAR CC PLANT

Plant: MM03 Manufacturing Plant, Vihar Vihar Chilling center,,Gandhinagar,382810

MAKING OF TUBEWELL (12"X900') USING A.C. CEMENT PIPES FOR VIHAR UNIT AS PER ATTACHED TECHNICAL SPECIFICATIONS.

Remarks:

Kindly consider additional specification for pre-survey of land geological testing for water availability before actual job execution, as per past bad experience of frequent failures of tube wells.

TUBEWLL (12"X900') USING A/C.CEMENT PIPING AS PER ATTACHED SPECIFICATIONS.

Kindly see attachment for detailed job description & specifications

Attachment :

- (1). Technical specifications.
- (2). Performance Criteria
- (3). Special Terms.

TECHNICAL CONTACT PERSONS:

- (1). M.S.THAKOR (I/C-ENGG/VCC)-(Mobile no:9974059273)
- (2). K.D. Chaudhari (Head Engg. & Chilling centres engg.)
-(Mobile no:99740 59275)

INSTRUCTIONS FOR SENDING QUOTATIONS

Send your quotations in hard copy (preferably) at following address to reach us before Quotation Deadline. Write Collective Number / RFQ No. on cover page of envelope. It is given in right corner of first page of RFQ.

Address for sending quotation:

Purchase Section

Mehsana District Co-operative Milk Producers Union Ltd.

Dudhsagar Dairy, Highway, Mehsana # 384002,

Phone: 02762-253201, Purchase Mobile No : +91 90237 27021 /22

Alternatively, you can send your quotations at quotation@mehsanaunion.coop. Do not send quotations on any other email ID. Kindly write Collective Number / RFQ No. on subject line.

Special Note : For RFQ having PDF Name (Manesar)/(Dharuhera), separate email address is given for sending quotation in last page of PDF. Kindly send your quotation to those email ID only.

Prior vendor registration is preferable but not necessary for sending quotation.

Goods to be supplied subject to terms and conditions available at <http://www.dudhsagardairy.coop/tenders/>



MEHSANA DISTRICT CO-OPERATIVE MILK PRODUCERS' UNION LIMITED

TECHNICAL SPECIFICATIONS & SPECIAL TERMS

Water Borewell for Vihar Milk Chilling Centre:

Site / location: Vihar Milk Chilling Centre

At Vihar Char Rasta, Taluka- Mansa, Dist.- Gandhinagar

Gujarat-388121

Description :

Making of bore well (12"x900') using A.C. Cement Pipes for vihar Milk chilling centre at Viha Char Rasta as per below technical specifications.

Remarks:

Kindly consider additional specification for pre-survey of land geological testing for water availability before actual job execution, as per past bad experience of frequent failures of tube wells.

Sl..	Description of Items	Oty./Unit	Make/Thick
1.	MAKING OF TUBE WELL FOR VIHAR.	1 JOB	
1.1	Pre-survey of land geological testing for water availability	1 job	
1.2	Preparation of temporary sump for water storage and refilling back after completion of drilling work.	1 job	
1.3	Labour work for drilling Bore well hole in any type of soil incl. of all tools & tackle – Hole Dia.-24" and up to above depth.	900 FT	
1.4	Conducting electro-logging test of 300mm dia. bore hole for above depth by providing electro logger unit at site and submission of report	1 JOB	
1.5	Lowering and packing good quality riverbed gravels of size 4mm to 6mm in well (Aaranda TYPE)	70MT (Approx.)	
3.	Supplying of reputed make A.C. Cement Casing piping (300 MM dia./12") with necessary fitting materials, Make	900 Ft	



MEHSANA DISTRICT CO-OPERATIVE MILK PRODUCERS' UNION LIMITED

	:Lotus/Hindustan/Kirti/Equiv.reputed.(Including requ.materials for jointing & labours up to lowering & aligining/laying)		
4.	Providing& fixing PVC Coupler,Galvanized Coupler,MS ball plug(Shoe) and MS Top cover with coupling and necessary all fitting materials	900 Ft.	
5.	Labour chages for making slot 1/16 or 1/8" size (making strainer pipe)	400 Ft.	
6.	Cement sealing by means of mud pump including cost of 20 or more bags cement, mud pump etc.	1 Job	
7.	Supplying clay ball made from stickle clay of size 15mm to 25mm.(apporx 50	CMT)30 CMT(Approx)	

Remarks: For further technical clarifications or site visit you may contact during office hours

To I/c.Vihar CC Sh P.N.Patel (Mob.-75748 63558)

OR

Engg I/c. at Vihar CC- Sh M.S.Thakor–Mob.99740 59273

OR

K.D. Chaudhari (Head Engg. & Chilling centres engg.)

-(Mobile no:99740 59275)



MEHSANA DISTRICT CO-OPERATIVE MILK PRODUCERS' UNION LIMITED

Battery Limits :

In scope of Bidder/ contractor :

Tube well: Entire drilling, reaming, logging, all casing pipes lowering & leveling with materials, Desired size & qty. of gravels packing, All necessary job work & all reqd. materials for tube well making up to top cover & side filling as such.

In scope of Dudhsagar Dairy:

Column Pipes : In Dudhsagar Dairy Scope.

Submersible Pump set : In Dudhsagar Dairy Scope.

Cabling : In Dudhsagar Dairy Scope.

Starter & electrification : In Dudhsagar Dairy Scope.

Performance Criteria :

- (1). Electro logging test result (Logging should be carried out by GWSSB / GWSSB approved agency)
- (2). Good quality water output without any sand (Sand free water), Should submit Govt. approved third party sand free report)
- (3) Desired water flow rate (Min. 50000 LPH)
- (4) Selection of good quality water zone (after electro logging test) having TDS at least less than 1200 PPM
- (5) Performance evaluation period- Min. 1 Year



MEHSANA DISTRICT CO-OPERATIVE MILK PRODUCERS' UNION LIMITED

1. Special Terms :

1. Your Rates will be on Firm Price Basis inclusive of Supply , Inspection, Installation, Freight, Loading & unloading, transit insurance. i.e. on FOR Vihar CC basis. On no other account increase/decrease in the price will be given during the order execution.
2. GST will be applicable @ 18 % as extra only if it is applicable to your Invoice.
3. Quantity - The RFQ quantity is an estimated quantity, which may vary depending upon actual requirement at site.
4. Payment: Payment will be released as per actual work done and certified by our user department. Payment will be released within 30 days from the date of satisfactory work completion or invoice whichever is later and if material & work is found as per approved specification.
5. Quality: The material must conform to our specifications in all respects. The supplies not conforming to our specifications will be rejected at your cost and risk.
6. You will have to start and complete the work strictly as per instruction by our incharge Vihar CC If due to unavoidable circumstances, contractor is not able to start work within maximum duration of 15 days after our intimation, contractor will have to inform our respective user department head by official communication to extend permissible work completion period.
7. You will have to depute competent Supervisor for execution of required work at site as well as for better communication to our sectional / departmental heads.
8. For any damage to union property by you, union will debit suitable amount in your payment.
9. For any accident, the contractor is sole responsible. No any liability of Mehsana Union.